

Sheridan Construction
Devon House
The Warren
Kingswood
KT20 6PQ

24th January 2019

Dear Seb

Estimate (subject to terms & conditions)
Subject to a final site survey when heating installed

Reference: Westcott

Further to your email I have enclosed an estimate based on 12.5m² to supply & install Camaro tiles as follows.

To supply Polyflor Camaro Tiles colour 2229 White Limed Oak	
4 Boxes @ 3.34m ² = 13.36m ² @ £39.00m ²	£521.00
Adhesive 5 KG high temp adhesive for under floor heating	£48.00
Labour for installation of tiles in one visit	£250.00
Total cost labour & materials	£819.00 + VAT @ 20%

As these tiles are only 2mm thick we may need to fit a smoothing screed over the under floor heating screed. Below are the costs if this is required.

To supply & lay aprox 3mm smoothing screed to 12.5m ²	
Total cost labour & materials	£340.00 + VAT @ 20%

Important – Notes re under floor heating & Camaro tiles

Under floor heating needs to be off prior to fitting and left off for 24hrs after installation. When heating is turned on it should be set low aprox 10 degrees and then increased daily by 2 degrees until it reaches normal operating temperature. Floor temperature should not exceed 26 degrees at any time when in use.

Customer's notes.

1. Both areas to be installed in one visit
2. The above estimate does not include cutting of doors.
3. All areas to be clear at time of fitting.
4. Works to be carried out between 9-5 Monday – Friday.
5. Above costs subject to a site survey & measure.

Assuring you of our best attention at all times.

Yours Sincerely

